

PREPARED FOR: Test Customer Inc. 123 Industrial Park, Block B Contact: +1 234 567 8900	SYSTEM SPECIFICATIONS: Dimensions: 2000W x 2000D x 2000H (mm) Pad Thickness: 150 mm Face Configuration: 4-face (Front, Back, Left, Right) Rate Card Ref: v1
--	--

COST SUMMARY

Item Description	Qty	Unit Price	Total
Cooling Pads	8	\$150.00	\$1200.00
Bottom Plate & Side Plates Sheeting	8	\$200.00	\$1600.00
Aluminium Frame Channels	8	\$80.00	\$640.00
Support Patti (Vertical joint posts)	3	\$60.00	\$180.00
Plumbing System & Piping Fittings	1	\$300.00	\$300.00
Water Pump (Pump A 2000LPH)	1	\$100.00	\$100.00
GRAND TOTAL (USD)			\$4020.00

* Quotation is valid for 30 days from the date of issue.

INTERNAL ENGINEERING MATERIALS LIST

Cooling Pads Details: - Total pads: 8 sheet(s) - Details per selected face: - Front: 2W x 1H = 2 pads - Back: 2W x 1H = 2 pads - Left: 2W x 1H = 2 pads - Right: 2W x 1H = 2 pads Pumps & Plumbing Sizing: - Flow required: 812.89 LPH - Selected Pump: Pump A 2000LPH (Capacity: 2000 LPH)	Metal & Frame Work: - Outer frame bars: 8 pcs - Total Length: 25680 mm - Patti (Vertical joints): 3 pcs - Patti posts count: 4 pcs - Plate sheets (bottom + sides): 8 pcs - Total Plate Area: 20000000 mm²
--	--