

QUOTATION

Quotation No. : QT-20261005-0019
 Date : 5/10/2026
 Valid Until : 15/10/2026
 Prepared By : SEETECH Solutions

Client Name : Adani
Contact Person : N/A
Contact Number : 987654321
Client Address : abc
Subject / Reference : Supply of Adiabatic Cooling Sizing Slabs / Frame Work

Sr. No.	Item Name	Description	HSN/SAC Code	QTY	Unit	Rate (₹)	Discount	Total Amount (₹)
1	Evaporative Cooling Pads	Cellular cellulose paper cooling pad 7090 NTK	-	7	nos	3,000.00	-	21,000.00
2	Aluminium Plate Sheeting	Bottom Plate & Side Plates Sheeting protective guards	-	3	pcs	2,800.00	-	8,400.00
3	Aluminium Outer Frame Channels	Outer supporting boundary aluminum frame bars	-	7	bars	700.00	-	4,900.00
4	Vertical Joint Support Patti	Vertical alignment joint support patti structures	-	3	bars	500.00	-	1,500.00
5	Plumbing Piping & Sizing fittings	Piping water distribution system and flow fittings	-	1	lot	100.00	-	100.00
6	Water Circulation Pump	Water pump (EcoFlow 1000)	-	1	no	200.00	-	200.00

Amount in Words: forty two thousand five hundred and ninety eight rupees only

Total Amount	₹ 36,100.00
Discount	₹ 0.00
Total Taxable Amount	₹ 36,100.00
CGST (9%)	₹ 3,249.00
SGST / IGST (9%)	₹ 3,249.00
Grand Total	₹ 42,598.00

Payment Terms:

Payment terms shall be as mentioned in the commercial summary of this quotation.

Terms & Conditions:

- GST shall be charged extra as applicable unless specifically stated otherwise.
- Delivery schedule shall commence from receipt of technically and commercially clear purchase order and agreed advance payment.
- Freight and transit insurance shall be as specified in the commercial summary.

QUOTATION

Quotation No. : QT-20261005-0019

Date : 5/10/2026

Valid Until : 15/10/2026

Prepared By : SEETECH Solutions



INTERNAL ENGINEERING MATERIALS LIST

Cooling Pads Details:

- Total pads: 7 sheet(s)
- Details per selected face:
 - Back: 3W x 1H = 3 pads
 - Left: 2W x 1H = 2 pads
 - Right: 2W x 1H = 2 pads

Pumps & Plumbing Sizing:

- Flow required: 711.28 LPH
- Selected Pump: EcoFlow 1000
(Capacity: 1000 LPH)

Metal & Frame Work:

- Outer frame bars: 7 pcs
 - Total Length: 19260 mm
- Patti (Vertical joints): 3 pcs
 - Patti posts count: 4 pcs
- Plate sheets (bottom + sides): 3 pcs
 - Total Plate Area: 13320000 mm²

Thank you for your business!

This quotation is confidential and intended solely for the recipient.